No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
22	Painting teakwood windows and doors with 2 coats of silicate paint	,,	3 8 0	17.82	
23	Painting rolled steel beams with 2 coats of green paint	,,	3 8 0	8.53	
24	Providing and fixing a collapsible gate in front	S.ft.	2 4 0	58	
25	Down water pipes	R.ft.	..	..	

N. KRISHNIENGAR,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification, dated 4th February 1936.

The attention of the public is invited to the notification on pages 214-215 of the issue of the *Mysore Gazette*, dated 13th February 1936, inviting tenders for the work of restoring Gollahalli Ayyavarakere, Register No. 518 of Bagepalli Taluk.

The last date fixed for the receipt of the tender in this office is 2 P.M. on 28th February 1936.

Abstract Notification, dated 6th February 1936.

The attention of the public is invited to the notification on pages 215-218 of the issue of the *Mysore Gazette*, dated 13th February 1936, calling for tenders for closing the breach and extending left waste weir of Thimmampalli Nayankere, Register No. 859 of Bagepalli Taluk.

The last date fixed for the receipt of tenders is 2 P.M. on 24th March 1936.

Notification, dated 17th February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 16th March 1936, for improvements to the feeder channel of Bodimarlur, Register No. 164, Goribidnur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M. of office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees Two Hundred in cash or Government Promissory Notes, as earnest money, and be superscribed 'Tender for improvements to the feeder channel of Bodimarlur Tank, Register No. 164, Goribidnur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Progress to the extent of Rs. 700 has to be shown every month.

Abstract estimate for constructing an Anicut Head Sluice and improvements to the feeder channel of Bodimarlur Tank, Register No. 164 in Goribidnur Taluk.

No.	Items of work	Per	Quantity	Rate	Cost
				Rs. a. p.	Rs. a. p.
	ANICUT.				
1	Earthwork excavation for foundation ..	C.yd.	1,900	0 2 9	
2	Do forming flank bund	,,	435	0 2 0	
3	Stone jelly concrete in surki mortari neluding lead	C.ft.	1,095	0 4 3	
4	Burnt stone in surki mortar	,,	2,898	0 4 6	
5	Burnt stone slab, 6" thick dressed ..	S.ft.	646	0 5 0	
6	Deep pointing with cement mortar ..	Sqr.	19.46	4 8 0	
7	Deep cement pointing over body-wall ..	,,	6.00	4 8 0	
8	Burnt stone sujee cut work	C.yd.	148	2 8 0	
9	Burnt stone slabs	Sq. ft.	580	0 5 0	
10	Cutting joggle joints	Each	35	1 0 0	
	Total ..	..	..	..	..
	HEAD SLUICE.				
1	Earthwork excavation for foundation ..	C.yd.	26	0 2 9	
2	Stone jelly concrete in surki mortar ..	C.ft.	190	0 4 3	
3	Burnt stone in surki mortar	,,	911	0 4 6	
4	Burnt stone slabs 6" thick dressed ..	Sq.ft.	143	0 5 0	
5	Cut stone work	C.ft.	4	1 0 0	
6	Deep cement pointing	Sqr.	6.59	4 8 0	
7	Cutting grooves in the slab	Each	10	0 12 0	
8	Providing Teakwood shutter with gearing rod, etc., complete	L. S.			
9	New stone work with jelly backing and wedging	C.yd.	133	1 12 0	
10	Excavating lead-off channel to head sluice	L. S.			
	Total ..	..	..	..	..
	IMPROVING THE FEEDER CHANNEL.				
1	Earthwork to bank with consolidation ..	C.yd.	183	0 4 0	
2	do cutting the channel	,,	66	0 2 9	
3	Turfing with good grass and forming the bank	Sq.yd.	356	0 0 9	

N. SUBBA RAO,
Executive Engineer.